

Branconnier and Dorzek-
Lemieux Drain 1994

Drain Maintenance

Project Scope

- Brushing/grubbing of Drains, approximately 1,257 meters, as per attached map.
- Bottom Clean Out and brushing.
- Drain Profile/grades are available and can be provided.
- Mobilization/demobilization/Floating/equipment/labour/traffic control plan shall be included in the lump sum bid price.

Brushing/Grubbing of Branconnier Drain A (274m): \$ 3493 / Lump Sum
Brushing/Grubbing of Branconnier Drain C (123m): \$ 1568 / Lump Sum
Brushing/Grubbing of Dorzek-Lemieux Drain B (265m): \$ 3379 / Lump Sum
Brushing/Grubbing of Dorzek-Lemieux Drain C (455m): \$ 5201 / Lump Sum
Brushing/Grubbing of Dorzek-Lemieux Drain D (140m): \$ 1785 / Lump Sum

} + HST.

Provisional Linear Meter Rate for Ditching and Brushing: \$ 12.75 / L. M.

Date of completion: 01/June/2004 (Day/Month/Year)

Notes

- Contractor responsible for ALL utility locates
- Slope laser shall be used
- Site visit recommended to ensure accurate bidding
- Work Schedule to be provided 5 working days in advance
- Affected property owners shall be notified minimum 5 days in advance
- Brushing can be either grubbing or power brush but all roots must be removed (root raked)
- Brush and spoil material to be separated and not mixed together
- Contract award is on Lump Sum basis

Excavator Make: Cat Model: 313

Company Name: Proficient Excavating

Company Representative

Name: Denis Jodan

Signature: [Signature]

* Please return quotes via e-mail